

**ADVERTISEMENT FOR BIDS FOR CONSTRUCTION OF
STREET RESURFACING
FOR THE
CITY OF HOMERVILLE, GEORGIA**

Sealed proposals will be received by the City of Homerville, Georgia at the City of Homerville City Hall, 20 South College Street, Homerville, Georgia 31634 until 10:00 a.m. local time, Tuesday, September 29, 2026 at which time and place they will be publicly opened and read. No submitted bid may be withdrawn after the scheduled closing time for receipt of bids for a period of sixty (60) days.

The Georgia Department of Transportation Standard Specifications, 2021 Edition, Supplemental Specifications Book, 2024 Edition, and applicable Supplemental Specifications and Special Provisions apply to this project.

The work to be done consists of furnishing all materials, equipment and labor for the construction of:

PART A – REDDICK STREET – D.O.T. P.I. # 0020461

The project will consist of patching, overlay with 816 tons of recycled asphalt concrete 12.5 mm Superpave, 989 gallons of bitum tack coat, restriping, traffic control, and appurtenances.

PART B – MCCONNELL ROAD – D.O.T. P.I. # 0020461

The project will consist of patching, 1134 square yards of 8" graded aggregate base course, overlay with 94 tons of recycled asphalt concrete 12.5 mm Superpave, 117 gallons of bitum tack coat, traffic control, restriping, and appurtenances.

PART C – MITCHELL LANE – D.O.T. P.I. # 0020461

The project will consist of 912 square yards of 10" full depth reclamation with 100 tons cement, 101 gallons of bitum tack coat, restriping, traffic control, adjusting 2 manholes to grade, and appurtenances.

PART D – MCGLASHIN CIRCLE D.O.T. P.I. # 0020461

The project will consist of patching, overlay with 85 tons of recycled asphalt concrete 12.5 mm Superpave, 109 gallons of bitum tack coat, restriping, traffic control, and appurtenances.

Time allotted for construction is 150 consecutive calendar days for substantial completion and 180 days for final completion.

Proposals for the complete work in one general contract shall be made on the proposal form provided and shall contain prices in words and figures for the work bid on.

All proposals shall be accompanied by a Bid Bond drawn in favor of the City of Homerville, in the amount of at least 5% of the lump sum bid for the complete work; such Bid Bond representing that the Bidder, if awarded the contract, will promptly enter into a contract and furnish Performance Bond and Payment Bond as provided by law and approved by the Attorney for the City of Homerville. Each bond shall be equal to 100% of the contract amount. The Bid Bond shall be forfeited to the City of Homerville as liquidated damages if the Bidder fails to execute the

contract and provide Performance and Payment Bonds within 10 days after being notified that he has been awarded the contract.

Drawings and Specifications are open to public inspection at the office of the City of Homerville and at the offices of Turnipseed Engineers in Atlanta and Augusta, Georgia.

Plans and specifications must be obtained at <https://turnipseed.com/current-projects/out-for-bid/>. One (1) digital copy of the plans and specifications and one (1) printed copy of the specifications (bid book) will be provided upon receipt of \$100. Upon request, one (1) printed full or reduced size set of drawings is available at no additional charge.

The Owner reserves the right to reject any or all bids and to waive informalities.

CITY OF HOMERVILLE, GEORGIA

By: 
Mayor Thomas E. Kennedy